CHROME

218 East State St
Rockford

EXISTING CONDITIONS

Rust should be scraped off of steel lintel with a wire brush and lintel should be painted black to match the new color scheme.

Salvaged Vitro-lite or another similar material should be installed to match the existing white Vitrolite.

chrome should be installed in vinyl graphics in font **MicrogrammaDEEBolExt** on the Vitrolite.

A chrome plated bar should be installed under the vinyl lettering. See the Vitrolite specialist for instructions on attaching metal to glass.

Aluminum should be scraped and repainted black to match new color scheme.

Vinyl window graphics with the business name, address, and hours of operation should be installed on the display windows and entry door.

Four New windows should be installed in the historic opening.

Paint should be carefully scraped from existing Vitro-lite. Vitrolite should be inspected and mastic reapplied where needed.

Historic doors should be retained, repaired as needed and repainted to match new color scheme.

PROPOSED DESIGN

OFFICE OF LIEUTENANT GOVERNOR PAT QUINN

ILLINOIS MAIN STREET PROGRAM

The Illinois Historic Preservation Agency, through the Illinois Main Street Program, has provided this free design assistance to qualified property/business owners in the officially designated Main Street district. This conceptual rendering is based on information supplied to the staff. Should obscured architectural details or problems be revealed during the work, the local project manager and/or the staff architects should be consulted.

ILLINOIS HISTORIC PRESERVATION AGENCY
One Old State Capitol Plaza
Springfield, Illinois 62701
217.782.4836
www.illinois-history.gov

Drawn by AMB	June, 2007
Project Number 2007030	Sheet 1 of 1